



REPUBLIKA PHILIPPINES

Pambansang Korporasyon Sa Elektrisidad
(NATIONAL POWER CORPORATION)

SMALL POWER UTILITIES GROUP - MINDANAO

PURCHASE ORDER

P.O. **008395(SVP)**

Page 1 of 1

This PO number must appear on all papers, invoices, packing list and correspondence.

TO: **F.H. GOPITEO CONSTRUCTION AND SUPPLY**
Poblacion Tupi, South Cotabato

DATE: **June 23, 2022**

PD NO.: **S3-DIN22-012**

PR DATE: **February 22, 2022**

DELIVER PERIOD: WITHIN **30** CALENDAR DAYS FROM DATE OF RECEIPT OF THIS ORDER

TERMS: 30 DAYS UPON DELIVERY AND SUBMISSION OF ALL DOCUMENTS STATED AT THE BACK HEREOF / COD / PREPAYMENT

DELIVER SITE:
PLANT-SITE, DINAGAT DPP

REQUISITIONER:
R. U. FULLIDO / Div. Mgr., EMOD

| PO ITEM NO. | PR NO./ ITEM NO. | DESCRIPTION | QTY | UNIT OF MEASURE | UNIT PRICE (P) | AMOUNT (P) |
|-------------|------------------|---|-----|-----------------|----------------------------|-------------------|
| 1 | 1 | REQUEST FOR SERVICES: Repair of Control Roof and Ceilings at Brgy. Wilson, San Jose, Dinagat DPP | 1 | LOT | | 448,214.29 |
| | | To furnish labor, materials and skills for the repair of Control room Roof, Ceilings and other related works located at Brgy. Wilson, San Jose, Dinagat Province: | | | | |
| | | Scope of Work to be done: | | | | |
| | | 1. Pull-out and replace/install 30 pcs of pre-painted (color roof – blue color) durarib galvanized roofings, 0.50mm thickness (16pcs – 8.30m length and 14pcs-4.95m length) | | | | |
| | | 2. Replace/install cover for the 3-span louvers with pre-painted (color roof – blue color) durarib galvanized roofs 0.50mm thickness | | | | |
| | | 3. Pull-out and replace all ceiling joist and use ¼" marine plywood measures 600mm x 1200mm for ceilings at control room including all lightings with 16 pcs-15 watts led bulbs | | | | |
| | | 4. Replace all dilapidated canopy ceilings at the back of control room and stockrooms use ¼ marine plywood and apply painting. | | | | |
| | | 5. Replace all downspouts 4" dia PVC and gutters with pre-painted (color roof –dark brown) galvanized sheet, 0.50mm thickness total length of 30 meters | | | | |
| | | 6. Painting of white gloss enamel for ceilings and gloss latex for concrete walls at control room | | | | |
| | | 7. Clean and dispose all waste materials to its designated area | | | | |
| | | | | | COST OF GOODS.....P | 448,214.29 |
| | | | | | TAX 12 %P | 53,785.71 |
| | | | | | TOTAL AMOUNT.....P | 502,000.00 |

THIS ORDER IS SUBJECT TO THE TERMS & CONDITIONS PRINTED AT THE BACK HEREOF:

| | | | | | | |
|---|----|----|----|----|---|---|
| CC | GL | OE | WO | JO | Pambansang Korporasyon Sa Elektrisidad | Please signify your acceptance and agreement with this P.O. By signing below: CONFORME: <u>Arvic Mangat</u> POSITION: _____ DATE: <u>6/27/22</u> |
| <p><u>6681026</u> <u>573</u> <u>676</u> <u>F253853</u></p> <p>FUNDS AVAILABLE</p> <p><u>ANNABELLE E. OGA</u> Financial Specialist</p> | | | | | BY | |
| | | | | | <p><u>YACOB H. DARAYAN</u> Department Manager, SPUG-MOD</p> <p>AUTHORIZED SIGNATURE</p> | |