



REPUBLIKA NG PILIPINAS  
**Pambansang Korporasyon Sa Elektrisidad**  
 (NATIONAL POWER CORPORATION)  
**SMALL POWER UTILITIES GROUP - MINDANAO**  
**PURCHASE ORDER**

P.O. **008462(SVP)**  
 Page 1 of 1  
 This PO number must appear on all papers, invoices, packing list and correspondence.

TO:

DATE: **August 31, 2022**

**MANUELA CONSTRUCTION SERVICES**

Bascon Petron, Purok Quezon, Brgy. Rotonda, Koronadal City

PD NO.: **S3-DIN22-019**  
 PR DATE: **April 12, 2022**

DELIVERY PERIOD: WITHIN **60** CALENDAR DAYS  
 FROM DATE OF RECEIPT OF THIS ORDER

TERMS: 30 DAYS UPON DELIVERY AND SUBMISSION OF ALL DOCUMENTS  
 STATED AT THE BACK HEREOF / COD / PREPAYMENT

**DELIVERY POINT:**  
 PLANT SITE- DINAGAT DPP

**REQUISITIONER:**  
 R. U. FULLIDO / Div. Mgr.- EMOD

PO ITEM NO.	PR NO./ ITEM NO.	DESCRIPTION	QTY	UNIT OF MEASURE	UNIT PRICE (P)	AMOUNT (P)
1	1	<b>REQUEST FOR JOB ORDER: To furnish labor, materials, tools and expertise for the repair of office and warehouse building at Brgy. Wilson, San Jose, Dinagat Province</b>	1	LOT		623,214.29
<b>TOTAL COST OF GOODS.....P</b> <b>TAX 12 % .....P</b> <b>TOTAL AMOUNT.....P</b>						623,214.29 74,785.71 <b>698,000.00</b>

- Scope of works to be done:
- A. ROOFING AND BUILDING BLANKETS:
1. Replace all roofing 0.45mm color roof corrugated sheets, steel fasteners and sealant hardware and accessories 143sq.m
  2. Replace Thermal Insulation 10mm thick polyethylene with aluminum foil on both faces above purlins 140sq.m
  3. Replace all fascia boards ½" x ½" x 12" fiber cement board including steel frame hardware and accessories – 15linear meter
  4. Replace gutter 2.0mm thick metallic plastic gutter including fasteners, sealant, hardware and accessories
  5. Replace downspout 3"uPVC pipe series 1000 including joint fittings, solvent and brackets – 15 linear meter
- B. CEILING
1. Replace 5mm (1/4") thick marine plywood with standard good lumber ceiling joist spacing 600mm x 600mm, apply anti-termite liquid treatment -140sq.m
- C. DOORS
1. Replace glass aluminum double swing door using 8mm thick clear glass One(1) whole piece per panel, heavy gage extruded 50 x 100mm anodized aluminum space 0.80 O.C.B.W – 1
- D. WINDOWS
1. Replace 1-unit awning window glass 600mm x 1925mm, 6mm thick clear glass on anodized aluminum frame – 1unit
- E. PAINTINGS
1. Repainting of all concrete surfaces – 498 sq.m
  2. Repainting of all wooden surfaces – 140 sq.m
- F. ELECTRICAL CONNECTION AND WIRINGS
1. Replace electrical wirings and fixture and accessories, excluding electrical panel, breakers, outlets and switched – 1lot
  2. Pin light assembly with 23 watts LED Bulb – 14 assy
  3. Fluorescent assemble with 40watts LED build, single type – 8assy

**ADDITIONAL TERMS & CONDITION**

1. Delivery shall be accompanied with Certificate of Warranty.
2. Upon acceptance, a warranty shall be required either by retention money or special bank guarantee equivalent to Five percent ( 5% ) of the contract price.

**THIS ORDER IS SUBJECT TO THE TERMS & CONDITIONS PRINTED AT THE BACK HEREOF:**

CC <u>GL</u> <u>OE</u> <u>WO</u> <u>JO</u> <b>0621026, NB GFC F358953</b> FUNDS AVAILABLE <b>ANNABELLE E. OGA</b> Financial Specialist	BY <b>YACOB H. DARAYAN</b> Department Manager, SPUG-EMOD AUTHORIZED SIGNATURE	Pambansang Korporasyon Sa Elektrisidad Please signify your acceptance and agreement with this P.O. By signing below: CONFORME: <b>AWB</b> POSITION: _____ DATE: <b>9/5/22</b>
--	---	---

Office Address: NPC SPUG MINDANAO OPERATIONS DEPT.

NPC Mintal Complex, Kumintang St., Mintal, Tugbok dist., Davao City

Tel Noe (902) 902-0657 & 902-0610