



REPUBLIKA NG PILIPINAS
Pambansang Korporasyon Sa Elektrisidad
 (NATIONAL POWER CORPORATION)
SMALL POWER UTILITIES GROUP - MINDANAO
PURCHASE ORDER

P.O. 008641(SVP)
 Page 1 of 1
 This PO number must appear on all papers, invoices, packing list and correspondence.

TO:
BOLTSMANN TRADING
 No. 43 Lupo Diaz St., Bo. Obrero, Brgy. 16-B Poblacion District, Davao City
 Tel No. (082) 282-3310

DATE: September 18, 2023
PD NO.:
PR DATE:

DELIVER PERIOD: WITHIN 30 CALENDAR DAYS FROM DATE OF RECEIPT OF THIS ORDER

TERMS: 30 DAYS UPON DELIVERY AND SUBMISSION OF ALL DOCUMENTS STATED AT THE BACK HEREOF / COD / PREPAYMENT

DELIVERY POINT:
PLANT SITE - DINAGAT DPP
Dinagat Island

REQUISITIONER:
L. A. ANDOY / Sr. Engr., DDPP

PO ITEM NO.	PR NO./ ITEM NO.	DESCRIPTION	QTY	UNIT OF MEASURE	UNIT PRICE (P)	AMOUNT (P)
1	1	S3-DIN23-024 (08/12/23) (OSO) REQUEST FOR JOB ORDER: Supply labor for the repair & maintenance of miscellaneous equipment Repair of various Air Conditioning unit (ACU) To furnish labor, tools, parts, refrigerant and expertise for the repair of leaks/servicing/cleaning and recharging of Freon. Scope of works: 1. Repair of leaks/servicing/cleaning and recharging of Freon of Inverter Type (Split) Air Conditioner Cooling capacity: 25,031 Btu/h / 26,408 kJ/h Indoor Model KV24WM-ARF21C2 Outdoor Model: KV240D-AR21C2 Brand: Koppel, Refrigerant R410A Location: Control Room and New Office Building 2. Repair of leaks/servicing/cleansing and recharging of Freon of package Type Air Conditioner Cooling capacity: 3 tonnes Brand: Carrier Refrigerant R410A Serial Number: 42BFMFSUCAR03TEAR12PC-0494511 Location: Control Room	1	LOT		33,250.00
2	1	S3-DIN23-025 (08/12/23) (G70) REQUEST FOR JOB ORDER: Fabrication and Installation for New location of Emission sampling port and platform intended for the 2 x 500kW MAN gensets Furnishing labor and materials for the additional fabrication and installation of sampling ports for stack emission testing in accordance to the requirements specified in Philippine Clean Air Act implementing Rules and regulations set by DENR for the 2 x 500kW MAN generator sets at Dinagat DPP 1. Fabrication of 4pcs steel sampling port 3"dia. With 4"length, flange type complete with bolts and nuts 2. Cutting of 4 holes preparation for sampling ports and installation of 2 pcs steel hock and 2pcs steel clip 3. Fabrication/Installation of steel flatform serve as easy access and working space during the conduct of sampling	1	LOT		43,732.14
ADDITIONAL TERMS & CONDITION					COST OF SERVICES.....P	76,982.14
1. Delivery shall be accompanied with Certificate of Warranty.					TAX 12 %P	9,237.86
2. Upon acceptance, a warranty shall be required either by retention money or special bank guarant equivalent to Five percent (5%) of the contract price.					TOTAL AMOUNT.....P	86,220.00

THIS ORDER IS SUBJECT TO THE TERMS & CONDITIONS PRINTED AT THE BACK HEREOF:

CC 068/026 GL 512 OE 050 WO 1670 JO
 FUNDS AVAILABLE
ANNABELLE E. OGA
 Financial Specialist 9-19-23

Pambansang Korporasyon Sa Elektrisidad
 BY **RODRIGO U. FULLIDO**
 Division Manager, SPUG-EMOD
 AUTHORIZED SIGNATURE

Please signify your acceptance and agreement with this P.O. By signing below:
 CONFORME: [Signature]
 POSITION: Gen. Manager
 DATE: 09/21/23